URBAN RIG Demo Test Operation Test Report

One World Techno Co., Ltd.

Experiment date and time	December 12, 2020	Weather	Sunny	Temperature	12°C	Start time	9:44	End time	5:52 PM
Request destination	One World Co., Ltd.								
Experiment Manager	Sakano				Driver		Itakura and Ishikawa		
Equipment used	4.8 ton machine (No. 2) URB-50-2	Fuel used	Heavy oil A: approx. 280		Power consumption			Water usage	
Object	450kg of waste tires								
Driving location	One World Techno Okayama Head Office Factory								

Pyrolysis Furnace Operation Setting Details

PR_0	Superheated steam		Pyrolysis Furnace		Boiler	Vapor SV5	Steam Burner B1	Heat Furnace Burner B2	Cooling Fan F1/F2	Suction Fan EP	Cooling Tower	MV1	MV2	PTL
STEP	Time	Temperature	Time	Temperature										
4	120	500	120	350	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
6	150	500	150	450	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
9	180	530	180	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
11	0	530	0	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
13	0	530	0	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
15	60	150	60	150	Stop	Close	Stop	Stop	Driving	Driving	Driving	Overheat	B	Yellow
16	1	0	1	0	Stop	Close	Stop	Stop	Driving	Driving	Driving	Overheat	B	Yellow

About processed materials

1. Photo before processing. Weight measurement

2. Photograph of the product placed inside the furnace before processing

3. Photograph of the product placed inside the furnace after processing

4. Photograph of the product placed inside the furnace after processing

Results and Discussion

450 kg of waste tires were pyrolyzed in stages. The waste tires were broken down into wire, charcoal, and oil.

The weight of each component after pyrolysis was 111 kg of wire, 133 kg of charcoal, and approximately 180 L of oil.

The next challenge is to shorten the processing time.

URBAN RIG Demo Test Operation Test Report								One World Techno Co., Ltd.	
Experiment date and time	December 12, 2020	Weather	Sunny	Temperature	12°C	Start time	9:44	End time	5:52 PM
Request destination	One World Co., Ltd.								
Experiment Manager	Sakano			Driver		Itakura and Ishikawa			
Equipment used	4.8 ton machine (No. 2) URB-50-2	Fuel used	Heavy oil A: approx. 280	Power consumption				Water usage	
Object	450kg of waste tires								
Driving location	One World Techno Okayama Head Office Factory								

Pyrolysis Furnace Operation Setting Details

PR_0	Superheated steam		Pyrolysis Furnace		Boiler	Vapor SV5	Steam Burner B1	Heat Furnace Burner B2	Cooling Fan F1/F2	Suction Fan EP	Cooling Tower	MV1	MV2	PTL
STEP	Time	Temperature	Time	Temperature										
4	120	500	120	350	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
6	150	500	150	450	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
9	180	530	180	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
11	0	530	0	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
13	0	530	0	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
15	60	150	60	150	Stop	Close	Stop	Stop	Driving	Driving	Driving	Overheat	B	Yellow
16	1	0	1	0	Stop	Close	Stop	Stop	Driving	Driving	Driving	Overheat	B	Yellow

About the temperature graph



Temperature graph line colors and measurement points

	TE 1	Steam temperature
	TE 2	Superheated steam outlet temperature
	TE 3	Superheated steam furnace inlet temperature
	TE 4	Combustion chamber temperature
	TE 5	Furnace lower temperature
	TE 6	Medium temperature inside the furnace
	TE 7	Furnace top temperature
	TE 9	Off-gas catalyst outlet temperature

URBAN RIG Demo Test Operation Test Report						One World Techno Co., Ltd.	
Experiment date and time	December 12, 2020	Weather Sunny	Temperature	12°C	Start time 9:44	End time	5:52 PM
Request destination	One World Co., Ltd.						
Experiment Manager	Sakano		Driver		Itakura and Ishikawa		
Equipment used	4.8 ton machine (No. 2) URB-50-2	Fuel used	Heavy oil A: approx. 280	Power consumption		Water usage	
Object	450kg of waste tires						
Driving location	One World Techno Okayama Head Office Factory						

Pyrolysis Furnace Operation Setting Details

PR_0 STEP	Superheated steam Time	Superheated steam Temperature	Pyrolysis Furnace Time	Pyrolysis Furnace Temperature	Boiler	Vapor SV5	Steam Burner B1	Heat Furnace Burner B2	Cooling Fan F1/F2	Suction Fan EP	Cooling Tower	MV1	MV2	PTL
4	120	500	120	350	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
6	150	500	150	450	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
9	180	530	180	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
11	0	530	0	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
13	0	530	0	530	Driving	Open	Driving	Driving	Driving	Driving	Driving	Overheat	B	Green
15	60	150	60	150	Stop	Close	Stop	Stop	Driving	Driving	Driving	Overheat	B	Yellow
16	1	0	1	0	Stop	Close	Stop	Stop	Driving	Driving	Driving	Overheat	B	Yellow

Regarding the photo after processing Weight after processing etc. Charcoal: 133 kg Metal (wire): 111 kg Oil: approx. 180 L

1. Condition inside the furnace after processing

2. Condition of oil discharged into the oil-water separator



3. After removal, during measurementWire1

4. After taking out, during measurementWire2

5. After removal, during measurementWire3

6. After taking out, during measurementWire4

7. After removal, during measurementWire5

8. After removal, during measurementWire6

9. After removal, during measurementWire7

10. After removal, during measurementWire8

11.Wire Measuring all at once

12. Measuring carbides together